

SURE-WELD®

G U I D E - S P E C

Sure-Weld® TPO MECHANICALLY-FASTENED ROOFING SYSTEM

January 2012

This **GUIDE-SPEC** is a brief outline of Carlisle's Sure-Weld Mechanically-Fastened Roofing System requirements and is intended for use as a submittal with a bid package. Specifiers and the Carlisle Authorized Roofing Applicator must comply with the applicable sections of Carlisle's Technical Manual prior to design or bid.

PART I GENERAL

1.01 DESCRIPTION

The **Sure-Weld Mechanically-Fastened Roofing System** incorporates 12', 10' or 8' wide, white, gray or tan 45, 60 or 80-mil thick scrim-reinforced Sure-Weld Thermoplastic Polyolefin (TPO) membrane. Insulation is mechanically fastened to an acceptable roof deck. Sure-Weld perimeter sheets (6' or 4' wide respectively) are installed along the building edges and field membrane sheets are mechanically fastened to the roof deck with the appropriate Carlisle Fasteners and Fastening Plates. Adjoining sheets of Sure-Weld membrane are overlapped and joined together with a minimum 1-1/2" wide hot air weld. Refer to the Thermoplastic Specification for the required number of perimeter membrane sheets and the required fastener spacing.

1.02 QUALITY ASSURANCE

- A. This roofing system must be installed by a Carlisle Authorized Roofing Applicator in compliance with shop drawings as approved by Carlisle.
- B. Upon request, an inspection shall be conducted by a Field Service Representative of Carlisle to ascertain that the membrane roofing system has been installed according to Carlisle's published specifications and details applicable at the time of bid. This inspection is to determine whether a warranty shall be issued. It is not intended as a final inspection for the benefit of the owner.
- C. For specific code approvals achieved with this system, refer to Carlisle's Sure-Weld Code Approval Guide, FM Approvals or UL Fire Resistance Directory for Roofing Materials and System.

1.03 SUBMITTALS

- A. To ensure compliance with Carlisle's warranty requirements, the following projects should be forwarded to Carlisle for review prior to installation, preferably prior to bid.
 - 1. Air pressurized buildings, canopies, and buildings with large openings, cold storage buildings or freezer facilities, adhered roofing system projects over 100' in height or projects where the membrane is expected to come in direct contact with petroleum-based products, waste products (i.e., grease, oil, animal fats, etc) and other chemicals.
- B. Shop drawings must be submitted to Carlisle by the Carlisle Authorized Roofing Applicator along with a completely executed Notice of Award (Page 1 of Carlisle's Request For Warranty form) for approval. Approved shop drawings are required for inspection of the roof and on projects where on-site technical assistance is requested.

1.04 GENERAL DESIGN CONSIDERATIONS

- A. It is the responsibility of the building owner or his/her designated representative to verify structural load limitation. In addition, a core cut may be taken to verify weight of existing components when the roofing system is to be specified on an existing facility.
- B. On new construction projects, especially in cold climate regions, moisture generated due to the construction process could adversely impact various components within the roofing assembly if not addressed. [Refer to Spec Supplement G-01-11 "Construction Generated Moisture" included in the Carlisle Technical Manual or SPRI Advisory Bulletin included in the Design Reference DR-03-11 "Construction Generated Moisture".]
- C. On structural concrete decks, when a vapor retarder is not used, gaps in the deck along the perimeter and around penetrations must be sealed along with vertical joints between tilt-up panels, if present, to prevent infiltration of hot humid air and possible moisture contamination resulting from condensation. This is specifically important when adhesive is used to attach the roof insulation.

CAUTION: If left unaddressed, collected moisture could weaken insulation boards and facers resulting in a blow-off or increase the probability of mold growth.



- A. Refer to Carlisle Technical Manual for applicable project specific Job Conditions.

PART II PRODUCTS

2.01 GENERAL

The components of this roofing system are to be products of Carlisle or accepted by Carlisle as compatible. The installation, performance or integrity of products by others, **when selected by the specifier and accepted by Carlisle**, is not the responsibility of Carlisle and is expressly disclaimed by the Carlisle Warranty.

2.02 MEMBRANE

Sure-Weld white, gray or tan 45, 60, 72, 80-mil thick reinforced Thermoplastic Polyolefin (TPO) membrane is used for this system. Field membrane sheets are 12', 10' or 8' wide by 100' long based on project conditions. Perimeter sheets are 6' wide (used with 12' or 10' field sheets), or 4' wide (used with 8' field sheets).

2.03 RELATED MATERIALS

Sure-Weld Non-Reinforced or Reinforced Flashing, Bonding Adhesive, Cut Edge Sealant, Water Cut-Off Mastic, Weathered Membrane Cleaner, Molded Pocket Sealant, Heat Weldable Walkway Pads, Pre-Molded Inside/Outside Corners, Pipe Flashings, Curb Wraps and Sealant Pockets.

PART III EXECUTION

3.01 GENERAL

- A. When feasible, begin the application at the highest point of the highest roof level and work to the lowest point to prevent moisture infiltration and to minimize construction traffic on completed sections. This will include completion of all flashings, terminations and daily seals.

3.02 ROOF DECK CRITERIA

- A. Proper substrate shall be provided by the building owner. The structure shall be sufficient to withstand normal construction loads and live loads.
- B. Defects in the roof deck must be reported and documented to the specifier, general contractor and building owner for assessment. The Carlisle Authorized Applicator shall not proceed with installation unless defects are corrected.
- C. Refer to Carlisle Technical Manual for acceptable decks and the applicable Sure-Seal Fasteners (when mechanical attachment of insulation is specified).

3.03 SUBSTRATE PREPARATION

- A. On retrofit-recover projects, cut and remove wet insulation, as identified by specifier, and fill all voids with new insulation so it is relatively flush with existing surface.
- B. For all projects, substrate must be even without noticeable high spots or depressions, and must be free of accumulated water, ice or snow.
- C. Clear the substrate of debris and foreign material. Fresh bitumen based roof cement must be removed or concealed.

3.04 INSTALLATION

Refer to the applicable Material Safety Data Sheets and Technical Data Bulletins for applicable cautions and warnings.

A. Insulation Attachment

1. Carlisle FAST Adhesive may be specified for insulation securement in full spray or beads with spacing as outlined in the Carlisle Technical Manual.
2. Carlisle Fasteners may be used, when specified, to secure Carlisle Insulation at the specified density outlined in the Carlisle Technical Manual.

B. Membrane Placement, Attachment and Hot Air Welding

1. A minimum of one perimeter sheet shall be installed at edges of each roof level and 12', 10' or 8' wide membrane shall be installed in the field of the roof.

2. Membrane sheets shall be mechanically fastened with the appropriate Carlisle Fastener/Fastening Plate spaced 6" to 12" on center, depending on project criteria, within the membrane splice. Refer to the Thermoplastic Specification for required number of perimeter membrane sheets and fastener spacing.
3. Overlap adjacent membrane sheets approximately 5-1/2" at those locations where Fastening Plates are located (along length of the membrane) and a minimum of 2" at end roll sections (width of the membrane).
4. Hot air weld the membrane sheets a minimum of 1-1/2" with an Automatic Hot Air Welding Machine.
5. Membrane that has been exposed to the elements for approximately 7 days must be prepared with Weathered Membrane Cleaner. Wipe the surface where Weathered Membrane Cleaner has been applied with a clean, dry HP Splice Wipe or other white rag to remove cleaner residue prior to hot air welding.

C. Additional Membrane Securement

The membrane must be secured at the perimeter of each roof level, roof section, expansion joint, curb, skylight, interior wall, penthouse, etc., at any angle change which exceeds 2" in one horizontal foot and at all other penetrations in accordance with Carlisle's Details published with Carlisle's Specifications.

D. Membrane Flashing

1. Flash all walls and curbs with Sure-Weld reinforced membrane. Non-Reinforced membrane shall be limited to inside and outside corners, field fabricated pipe seals, scuppers and Sealant Pockets where the use of pre-molded accessories are not practical.
2. On vertical surfaces, such as walls, curbs and pipes, Bonding Adhesive is not required when the flashing height is 12" or less and the membrane is terminated under a metal counterflashing (nailed). When a coping or termination bar is used for vertical terminations, Bonding Adhesive may be eliminated for flashing heights 18" or less.
3. Terminate the flashing in accordance with an appropriate Carlisle Details above anticipated slush line.
4. When using the Pressure-Sensitive Cover Strip to overlay metal edging flanges or fasteners/plates, Carlisle Weathered Membrane Cleaner is used to clean surfaces as needed. Apply Carlisle HP-250 Primer prior to applying Pressure-Sensitive Cover Strip.

Copyright 2012 Carlisle Construction Materials Incorporated

Carlisle, Sure-Weld, Interlocking Pavers are Trademarks of Carlisle Construction Materials Incorporated

Carlisle SynTec
P. O. Box 7000, Carlisle, PA 17013-0295
Phone: 800-479-6832
<http://www.carlisle-syntec.com>

Physical properties of Sure-Weld Membrane can be referenced in Part II, "Products" of the Thermoplastic Specification.

Attach copies of the applicable Carlisle Details that pertain to the individual project to complete a bid package submittal.