

CSI SECTION 03 60 00 – GROUTING 03 62 00 – NON-SHRINK GROUTING 03 62 13 – NON-METALLIC NON-SHRINK GROUTING

Fast-Setting, Non-Metallic, Multi-Purpose, Cementitious, Non-Shrink Grout

EDITOR NOTE: The following guideline specification has been prepared to assist architects and design professionals in the preparation of project master specifications. It is intended for use by qualified design professionals and is not intended to be used verbatim. Appropriate modifications to meet specific project requirements are required. Make appropriate [selections] where options are provided and delete items that are not applicable to the project. Contact CTS Cement Technical Service for additional information or project specification assistance.

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. Supply and installation of a non-shrink, fast setting, non-metallic high strength cementitious grout for anchoring, patching, casting and repairing concrete substrates in structural and non-structural applications.

1.2 RELATED SECTIONS

- [A. Section 03 01 00 Maintenance of Concrete
- B. Section 03 01 40 Maintenance of Precast Concrete
- [C. Section 03 01 50 Maintenance of Cast Decks and Underlayment
- [D. Section 03 01 60 Maintenance of Grouting
- [E. Section 03 01 80 Maintenance of Concrete Cutting and Boring
- [F. Section 03 30 00 Cast-in-Place Concrete
- G. Section 03 40 00 Precast Concrete
- [H. Section 03 50 00 Cast Decks and Underlayment
- [I. Section 03 54 16 Hydraulic Cement Underlayment
- [J. Section 03 70 00 Mass Concrete
- [K. Section 04 01 00 Maintenance of Masonry
- L. Section 04 20 00 Unit Masonry
- [M. Section 05 05 19 Post-Installed Concrete Anchors

1.3 REFERENCES

- A. AST C78 Test Method for Flexural Strength of Concrete
- B. ASTM C109 Standard Test Method for Compressive Strength of Hydraulic Cement

Mortars

C. ASTM C150 Standard Specification for Portland Cement

D. ASTM C191 Test Method for Time of Setting of Hydraulic Cement by Vicat Needle E. ASTM C266 Standard Test Method for Time of Setting of Hydraulic-Cement Paste by Gillmore Needles

F. ASTM C348 Standard Test Method for Flexural Strength of Hydraulic-Cement Mortars G. ASTM C939 Test Method for Flow of Grout for Preplaced Aggregate Concrete (Flow Cone Method)

H. ASTM C1090 Standard Test Method for Measuring Changes in Height of Cylindrical Specimens of Hydraulic-Cement Grout

I. ASTM C1107 Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Non-shrink)

J. ACI 301 Specification for Structural Concrete

- K. ACI 318 Building Code Requirements for Structural Concrete
- L. CRD-C 621 Corps of Engineers Specification for Non-Shrink Grout

1.4 SUBMITTALS



A. General: Submit samples and manufacturer's product data sheets, installation instructions, etc. in accordance with Division 01 General Requirements Submittal Section.

B. Test Data: Submit qualified testing data that confirms compliance with specified performance requirements.

1.5 QUALITY ASSURANCE

A. Qualifications:

1. Manufacturer:

a. Must have marketed non-shrink grouting materials in the United States for at least five years and must have completed projects of the same general scope and complexity.

b. Grout and complementary admixture materials must be manufactured by or approved for use by CTS Cement Manufacturing Corp. (800-929-3030, <u>www.CTScement.com</u>) and distributed by the same or an authorized CTS Cement dealer.

2. Applicator:

a. Must be experienced and competent in installation of rapid hardening, non-shrink grouting materials and provide evidence of a minimum of five years experience in work similar in size and scope to that required by this section.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Delivery: Deliver products in original, unopened, undamaged packaging with manufacturer's identification (i.e., brand logo, product name, weight of packaged unit, lot number).

B. Storage: Store products in a dry location, covered, out of direct sunlight, off the ground, and protected from moisture. Maintain storage temperature required by the manufacturer. Keep materials dry until used. Store bulk sand in a well-drained area on a clean, solid surface. Cover sand to prevent contamination.

C. Handling: Handle products in accordance with manufacturer's published recommendations.

1.7 SITE / ENVIRONMENTAL CONDITIONS

A. Temperature: Maintain ambient and surface temperatures between 45°F (7°C) to 90°F (32°C). Do not apply grout materials if ambient temperature falls below 45°F (7°C) within 24 hours of application. Protect grout from uneven and excessive evaporation during dry weather, windy conditions and strong blasts of dry air.

B. Inclement Weather: Do not apply grout materials during inclement weather unless appropriate protection is employed.

C. Sunlight Exposure: Avoid, whenever possible, installation of grout materials in direct sunlight which could adversely affect aesthetics.

D. Substrate: Prior to installation, the substrates must be inspected for surface contamination or other conditions that may adversely affect the performance of the grouting materials and be free of residual moisture.

1.8 COORDINATION AND SCHEDULING

A. Coordinate installation of grout materials with all other trades to avoid impeding other construction.

B. Sufficient manpower must be provided to ensure continuous application and timely finishing.

PART 2 - PRODUCTS



2.1 MANUFACTURERS

A. Basis of Design: CTS Cement Manufacturing Corp., 12442 Knott Street, Garden Grove, CA 92841 (800-929-3030, www.CTScement.com).

B. Components: Obtain grout and complementary admixture materials manufactured by CTS Cement from authorized distributors. No substitutions or additions of other materials are permitted without prior written permission from the manufacturer for this project.

2.2 MATERIALS

A. Fast Setting, Non-Shrink, Cementitious Grout

1. CementAll®: a pre-packaged, high-performance, fast-setting, multi-purpose, non-metallic, cementitious, non-shrink grout and concrete repair material mixed with water on site. Suitable for use in wet environments and any application where high durability and rapid strength gain are desired. Structural strength is achieved in one (1) hour. Suitable for structural and non-structural applications.

2. Additives and admixture materials must be approved for use by CTS Cement Manufacturing Corp. prior to use. (800-929-3030, www.CTScement.com)

B. Water: Clean, potable water free of deleterious amounts of silt and dissolved salts.

2.3 MATERIAL PROPERTIES

A. Fast Setting, Non-Shrink, Cementitious Grout

1. Compliance with: ASTM C1107 Grade B, ASTM C1090, Corps of Engineers CRD-C 621.

2. Minimum performance requirements:

Set Time	Initial Set	15 minutes
(ASTM C191 Modified)	Final Set	35 minutes
Compressive Strength (ASTM C109 Modified)	1 Hour* 3 Hours 1 Day 7 Days 28 Days	3,000 psi 5,000 psi 6,000 psi 7,000 psi 9,000 psi

Data obtained at flow consistency 102 by ASTM C1437 *After final set

2.4 RELATED MATERIALS

A. Admixtures: Do not add additional dry materials such as cement, sand, additives or admixtures. Mix only with water. All additives and admixture materials must be approved for use by CTS Cement Manufacturing Corp. prior to use. (800-929-3030, www.CTScement.com)

B. Concrete Cleaner: Citrus-based concrete cleaner to clean and strip dirt, grease and laitance from surfaces to receive grout.

- C. Curing: Prevent rapid water loss from grout during the first 48 hours by use of 1. Wet Burlap Method
 - 2. Curing Compound compliant with ASTM C309 Type I, Class B.

PART 3 – EXECUTION



3.1 EXAMINATION

A. Verify project site conditions under provisions of Section 01 00 00.

B. Compliance: Comply with manufacturer's instructions for installation of grouting materials.

C. Coordinate installation with adjacent work to ensure proper sequencing of construction.

D. Protect adjacent and surrounding surfaces not specified to receive grout with necessary means to ensure protection against overspray, water or other harmful debris.

E. Advise Contractor of discrepancies preventing proper installation of grouting materials. Do not proceed with the work until unsatisfactory conditions are corrected.

3.2 PREPARATION

A. Mechanically roughen surfaces and remove all loose, unsound, contaminated material.

B. Bonding surfaces must be clean, sound, and free from any materials that may inhibit bond such as oil, dirt, asphalt, sealing compounds, acids, wax and loose dust and debris.

C. Reinforcing steel must be free from rust and all other materials that may inhibit bond.

EDITOR NOTE: Add special requirements related to the replacement of reinforcement that has lost too much cross sectional area.

D. Apply Cement All to a surface that is thoroughly saturated with no standing water.

E. Minimum substrate temperature must be 45°F (7°C) and maximum substrate temperature 90°F (32°C).

F. For formed grouting applications, construct watertight, non-absorbent forms. Build forms 1 inch higher than the bottom of the plate and 1 to 3 inches between the side of the plate and the form.

G. Joints must be sealed with foam, caulk or putty.

H. Provide vent holes to avoid air entrapment.

I. Provide a head placement of a 45 degree angle to facilitate placement for grout pour.

3.3 MIXING

A. Cement All®: Comply with manufacturer's printed instructions and the following:

1. Organize installation personnel and equipment before mixing begins.

2. Cement All may be mixed using 3 to 3.75 quarts (2.8 L to 3.5 L) of water per 55-lb (25 kg) bag for Department of Transportation projects and other critical applications. For general purpose and high fluidity applications, a maximum of 5 quarts (4.7 L) may be used. Use less water to achieve higher strengths.

a. Additives: To extend working time, use Rapid Set® SET Control retarding admixture or cold mix water. To increase fluidity and workability, use Rapid Set® FLOW Control plasticizing admixture. Any other additives or admixture materials must be approved for use by CTS Cement Manufacturing Corp. prior to use. (800-929-3030, www.CTScement.com)

3. Add water to the mixing container. While mixing in a power driven mechanical mixer, such as a mechanical mortar mixer or drill mounted mixer, add CementAll®. Mix for the minimum time required to achieve a lump-free, uniform consistency (approximately 1 to 3 minutes). Do not retemper.



4. Never mix by hand. Do not re-temper, add water, or remix after the grout stiffens. Grout that stiffens before use must be discarded.

3.4 APPLICATION

A. CementAll®: Comply with manufacturer's printed instructions and the following:

1. Verify that all substrates and ambient temperatures are between 45°F (7°C) to 90°F (32°C) and will remain within range until the grout has reached final set.

2. Have all required tools, equipment and materials organized and as close to the grouting area as possible.

3. Place, consolidate and screed quickly to allow for maximum finishing time. Use a method

of

consolidation that eliminates air voids.

4. Material may be troweled, floated or broom finished. On flat work, do not install in layers. Install in full-depth sections and progress horizontally.

5. Do not wait for bleed water. Apply final finish as soon as possible.

3.5 CURING

A. Wet cure grout materials by keeping all exposed surfaces wet for a minimum of one (1) hour. Begin curing as soon as the surface starts to lose its moist sheen.

OPTION: Apply curing compound in accordance with ASTM C309 immediately after finishing or upon final set. Apply curing compound to all exposed grout surfaces after forms are removed.

3.6 CLEAN-UP

A. Remove and legally dispose of grouting debris material from job site.

B. Clean excess material from surrounding areas and all tools immediately, before material cures. If materials have cured, remove using mechanical methods that will not damage the substrate.

C. Clean adjacent surfaces as needed using materials and methods recommended by the manufacturer of the material being cleaned. Remove and replace work that cannot be cleaned to the satisfaction of the Project Designer/Owner.

END OF SECTION

Rev. April 2020

This sample guideline specification is intended for use by a qualified design professional. The sample guideline specification is not intended to be used verbatim as an actual specification without appropriate modifications for the specific project requirements.