



TECHNICAL BULLETIN 113

MIXING GROUTS IN Ready Mix Trucks

Certain Five Star® Grouts may be mixed via 3,000 lb. bulk bags in ready mix trucks. These include Five Star® Grout, Five Star® Cementitious Underwater Grout, Five Star® Special Grout 120, Five Star® Special Grout 150, and Five Star® Fluid Grout 100. Contact Five Star Products' Engineering and Technical Service Center at 1-800-243-2206 to verify the grout in question may be mixed in a ready mix truck, and for proper aggregate extension guidelines.

To mix Five Star® Grouts in 3,000 lb. bulk bags at a pre-determined coarse aggregate extension follow these guidelines:

- A. Verify working time of grout and water requirements under jobsite conditions before placement in ready mix trucks, particularly under hot weather conditions. Additional set retarders such as Five Star® Summerset may be required. Determine the amount of grout to be mixed per truck. Do not mix more than (3) x 3,000 lb. bulk bags per truck. **IMPORTANT** – Before commencing any bulk bag project, consult with Five Star Products and your local technical representative.
- B. Mixing drum and mixing blades must be in good operating condition, pre-dampened, and all excess water / washout removed. Trucks should be designated to arrive at job site with 80% of total mix water and 100% of pre-determined coarse aggregate (clean, damp 3/8" pea gravel meeting ASTM C33 or similar type). Ready mix plant must provide batch certification on water content and aggregate for each truck on site. It is advisable to pre-test aggregate before use with any Five Star® Grouts.
- C. Alternatively, aggregate may be added on site. Trucks should arrive at job site with 80% of total mix water. Utilizing a scale and a loader, the aggregate can be properly weighed and added (clean, damp 3/8" pea gravel meeting ASTM C33 or similar type). It is advisable to pre-test aggregate before use with Five Star® Grouts.
- D. Provide shading during grout placement and where feasible, place grout when temperatures are decreasing, at night or early morning. Provide protection from excessive wind to reduce rapid drying and evaporation of water from exposed grout surfaces.
- E. Add the grout with drum turning at slow speed. After loading the last bulk bag, use approximately 5 gallons of held back water to wash down the hopper and drum. Mix thoroughly for 5 minutes after the last bulk bag is loaded.
- F. Reverse the drum to check consistency. Add only as much of the remaining water as needed. Increase the drum speed to high and mix for 5 additional minutes to uniform consistency. Do not exceed the maximum allowable water content. Extra 50 lb. bags of applicable grout should be available to stiffen consistency if necessary.
- G. Position the truck as close as possible to the pour and promptly discharge the grout. It is recommended that the grout pass through a screen to remove any clumps prior to entering the pump hopper.



Five Star Technical Bulletins are provided for informational purposes only and should be used as general guidelines for consideration by contractors and engineers. While every reasonable effort has been made to ensure this information is accurate and authoritative, Five Star Products does not warrant the accuracy or completeness of this information, or its appropriateness for any particular purpose. The user of these documents remains solely responsible for the specification of all methods, materials and practices.

FIVE STAR PRODUCTS, INC.
60 Parrott Drive
Shelton, CT 06484 USA
Phone: +1 203-336-7900
Support: 1-800-243-2206 (IN THE U.S.)

For information 1-800-243-2206 • FiveStarProducts.com