The KeyCurb™ System Gives Your Roller Supports a Solid Base and Can Be Designed to Fit Almost Any Complex Installation. Choose from the Low Profile or the Extension Height Models. KeyCurb Units do Not Need Support Pads and are Easy to Install.

SPECIFICATIONS:

KeyCurb: Molded recycled rubber - each unit is 6" wide by 10" long, by 4.88" high. 5 lbs.

Load: Designed to support pipe diameters from 1/2" to 4" with a maximum pipe load not to exceed 150 lbs per ten foot spacing.

Roller: Molded plastic 3 1/2" wide.

Extension Models Include: Includes (2) adjustable carbon steel threaded rods and fastening hardware.

Installation: Position supports not to exceed 10 foot centers and check each support for equal weight distribution. Roller Extension models height can be adjusted up to 13" above the roof deck. Consult with roofing manufacturer's requirements.

Warranty: 5 years.

Maintenance: Normal maintenance is not required. However, semi-annual inspection by the owner is recommended. Inspection shall include checking pipe alignment, weight distribution and proper installation of bolts and nuts.



RKCRN1-4

QTY	MODEL	DESCRIPTION
	RKCRN1-4	ROLLER SERIES: Includes (1) KeyCurb with non-adjustable roller mounted on (2) galvanized mounts. Roller is plastic. Supports pipe diameters up to 4". Overall height is 9.66".
	RKCRE1-4	ROLLER EXTENSION SERIES: Includes (1) KeyCurb, and (2) adjustable carbon steel threaded rods which support the roller hanger. Roller is plastic. Supports pipe diameters up to 4". Overall height 13".



RKCRE1-4





Distributor:	Quantity:	
Contractor:	Approved By:	
Model #:	Architect:	
Project:	Date: © 2017 Activar Construction Products Group, Inc	