

CEMENT MASONRY VENEER Guide Specification
PermaBASE Building Products, LLC provided by National Gypsum Company

*(Specifier Note: The purpose of this guide specification is to assist the Specifier in correctly specifying cement board supported adhered masonry. The Specifier needs to edit these guide specifications to fit the needs of each specific project. Contact a **National Gypsum Company** representative to assist in appropriate product selections. Throughout the guide specification, there are Specifier Notes to assist in the editing of the file. Brackets []; "AND/OR"; and "OR" have been used to indicate when a selection is required, in most cases the first option is the standard feature.*

National Gypsum Company is the exclusive service provider of products manufactured by Gold Bond Building Products, LLC; PermaBASE Building Products, LLC and ProForm Finishing Products, LLC.

References have been made within the text of the specification to current MasterFormat Section numbers and titles. The Specifier needs to coordinate these numbers and titles with sections included for the specific project.)

SECTION 04 30 16
CEMENT BOARD SUPPORTED ADHERED MASONRY VENEER

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Cement board
2. Installation materials including adhesives, mortars, and pointing mortars.
3. Masonry: [**Thin Brick Veneer**] [**Manufactured Stone Veneer**] [**Natural Stone Veneer**] [**Insert type of masonry to be used**]

B. Related Requirements:

1. Division 7 Weather Barrier section(s).
2. Division 7 Joint Protection section(s).

1.2 REFERENCES

A. American National Standards Institute (ANSI)

1. ANSI A118.4 – Modified Dry-Set Cement Mortar.
2. ANSI A118.5 – Improved Modified Dry-Set Cement Mortar.
3. ANSI A118.9 – Test Methods and Specifications for Cementitious Backer Units.

B. ASTM International (ASTM)

1. ASTM C67 - Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile.
2. ASTM C91 - Standard Specification of Masonry Cement.

3. ASTM C109 - Standard Test Method for Compressive Strength of Hydraulic Cement Mortars.
 4. ASTM C270 - Standard Specification for Mortar for Unit Masonry.
 5. ASTM C473 - Standard Test Methods for Physical Testing of Gypsum Panel Products.
 6. ASTM C1002 - Standard Specification for Steel Self Piercing Tapping Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs.
 7. ASTM C1088 - Standard Specification for Thin Veneer Brick Units Made From Clay or Shale
 8. ASTM C1325 - Standard Specification for Non Asbestos Fiber Mat Reinforced Cementitious Baker Units.
 9. ASTM C1670 - Standard Specification for Adhered Manufactured Stone Masonry Veneer Units
 10. ASTM C1780 - Standard Practice for Installation Methods for Adhered Manufactured Stone Masonry Veneer
 11. ASTM D3273 - Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber.
 12. ASTM E72 - Standard Test Methods of Conducting Strength Test of Panels for Building Construction
- C. ICC - International Code Council Evaluation Service (ICC-ES):
1. ICC-ES AC 308: Acceptance Criteria for Reinforced Cementitious Concrete Used As Wall Sheathing and Floor Underlayment
- D. ISO - International Organization for Standardization
1. ISO - 13007: Ceramic Tiles -- Grouts and adhesives

1.3 ADMINISTRATIVE REQUIREMENTS

(Specifier Note: Preinstallation meeting is critical for this work result. Coordinate requirements with Division 01 Section - Project Management and Coordination.)

- A. Preinstallation Meeting: At the Project site **[a minimum of one week prior to commencing Adhered Masonry Work]**.

1.4 SUBMITTALS

- A. Refer to Section **[01 33 00 Submittal Procedures]** **[Insert section number and title]**.
- B. Manufacturer Warranty: Submit project specific letter of intent to provide specified warranty of installation system.
- C. Product Data: Submit current product literature for each product used in assembly.
- D. Samples: Masonry and Mortar selection.
- E. Reports:

1. Third party building code evaluation report indicating cement board is approved for use in exterior application in accordance with ICC-ES AC 308.

(Specifier Note: Sustainable Design Submittals may be required for projects pursuing certification by a 3rd party such as USGBC LEED program or Green Globes.)

F. Sustainable Design Submittals

1. Documentation indicating products fabricated within 500-mile radius of the Project Site from materials that have been extracted, harvested, or recovered within 500 miles of the Project Site.

(Specifier Note: Retain if Healthcare or Schools projects under LEED V4 or any interior application.)

2. VOC content of adhesive materials.

1.5 QUALITY ASSURANCE

A. Mock-ups

(Specifier Note: DELETE if mock-ups are not desired for specific project.)

1. Adhered masonry mock-up shall incorporate surrounding construction, including wall assembly, fasteners, flashing, and other related accessories installed in accordance with manufacturer's installation methods.
 - a. Mock-up size: **[Insert size] [As indicated on drawings.]**
 - b. Mock-up may **[not]** remain as part of the work.

1.6 DELIVERY, STORAGE AND HANDLING

- A. Refer to Section **[01 60 00 Product Requirements] [Insert section number and title]**.
- B. Protect masonry to prevent staining, chipping, spalling or contamination caused by water, freezing, foreign matter, and other adverse conditions.
- C. Store installation materials in a dry location, in accordance with manufacturers' recommendations.

1.7 FIELD CONDITIONS

- A. Maintain ambient temperature to comply with manufacturers requirements, during installation and for a minimum of seven days after completion of adhered masonry work.

(Specifier Note: Exposure to carbon dioxide can cause a chemical change in cementitious products. This will affect both the Cement Board and potentially the masonry.)

- B. Vent temporary heaters to the exterior to prevent carbon dioxide damage to cementitious products.

1.8 WARRANTY

A. Refer to Section **[01 78 36 Warranties]** **[Insert section number and title]**.
(Specifier Note: Include paragraph below if specifying LATICRETE system. Insert warranty requirements from other manufacturers, if applicable)

B. [Provide manufacturer 15 Year Warranty for the Exterior Cement Board Supported Adhered Masonry Veneer wall assembly.]

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Cement Board

1. Basis of Design: PermaBASE® Cement Board manufactured by PermaBASE Building Products LLC provided by National Gypsum Company, Charlotte, NC.
2. Subject to compliance with requirements, other manufacturers providing materials may include:
 - a. Other manufacturers complying with product substitution requirements as defined in Division 1.
3. Characteristics
 - a. Manufactured in accordance with ASTM C1325 and ANSI 118.9
 - b. Shear Bond Strength: greater than or equal to 200 psi, when tested in accordance with ANSI 118.4
 - c. Approved for exterior use in accordance with ICC-ES AC 376
 - d. Mold resistant panel score of 10 when tested in accordance with ASTM D3273

(Specifier Note: Select below for PermaBASE Cement Board)

- e. Core consisting of cement **[, polystyrene beads,]** and aggregates. Both faces to have embedded fiberglass mesh.
- f. Face Finish:
 - 1) Unexposed face: smooth finish
 - 2) Exposed face: cementitious finish

(Specifier Note: Select below for PermaBASE Cement Board)

- g. **[Moisture absorption of less than 8 percent when tested in accordance with ASTM C473.]**
- h. Thickness: **[1/2 inch (13 mm)] [5/8 inch (16 mm)]**
4. Accessories
 - a. Tape: 4 inch (102 mm) wide polymer-coated (alkali resistant) meshtape.
 - b. Fasteners: Drill point screws (No. 8) wafer head, corrosion-resistant, Type S-12 screws or equivalent, complying with ASTM C1002. Minimum 1-5/8 inches (41 mm) long.

B. Modified Dry-Set Cement Mortar

1. Basis of Design: LATICRETE® Masonry Veneer Mortar by LATICRETE International, Inc., Bethany CT
2. Subject to compliance with requirements, other manufacturers providing materials may include:
 - a. Mer-Krete Systems/Parex USA.
 - b. TEC, H.B. Fuller Construction Products, Inc.
 - c. Other manufacturers complying with product substitution requirements as defined in Division 1.
3. Characteristics
 - a. Preblended and Bagged Latex-Portland Cement Mortar
 - b. Weather, frost, shock resistant, and non-flammable
 - c. Compressive strength per ASTM C270: greater than or equal to 2400 psi when tested in accordance with ASTM C109.
 - d. Shear Bond Strength: greater than or equal to 300 psi when tested in accordance with ANSI A118.4
 - e. Sag on Wall: 0.0 mm in accordance with ISO 13007.

C. Pointing Mortar

1. Basis of Design: LATICRETE® Masonry Pointing Mortar by LATICRETE International, Inc., Bethany CT
2. Subject to compliance with requirements, other manufacturers providing materials may include:
 - a. Mer-Krete Systems/Parex USA.
 - b. TEC, H.B. Fuller Construction Products, Inc.
 - c. Other manufacturers complying with product substitution requirements as defined in Division 1.
3. Characteristics:
 - a. Compressive Strength: Minimum 3000 psi in accordance with ASTM C91
 - b. Color: **[46 Quarry Red] [24 Natural Grey] [44 Bright White] [45 Raven] [66 Chestnut Brown] [38 River Rock] [40 Latte] [39 Mushroom] [58 Terra Cotta] [Custom Color]**

E. Potable Water

2.2 MASONRY VENEER

(Specifier Note: Many types of masonry may be used in the assembly including thin brick, thin stone and manufactured stone. EDIT characteristics to match project specific requirements.)

A. **[Thin Brick] [Manufactured Stone] [Natural Stone Veneer]: [Product Name and Manufacturer].**

3. Obtain **[Thin Brick] [Manufactured Stone] [Natural Stone Veneer]** from a single source.

B. Characteristics:

3. Maximum Veneer Unit Weight: 15 psf.
4. Compressive Strength: 5 sample avg. 2,200 psi. 1500 psi minimum for individual unit.
5. Shear Bond Strength Between Stone Unit, Latex-Portland Cement Mortar, and Cement Substrate: greater than or equal to 300 psi when tested in accordance with ANSI A118.4.
6. Freeze/Thaw: ASTM C67, no disintegration and less than 3 percent weight loss.
7. Grade: **[Insert desired grade]**
8. Size: **[Insert size]**
9. Edge: **[Insert edge type]**
10. Finish: **[Insert Finish if applicable]**
11. Color: **[Insert selected color]**

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify wall assembly has been installed in accordance with Contract Documents including:

(Specifier Note: Structural design and deflection requirements should be governed by the masonry manufacturer requirements. As a rule of thumb limit deflection to L/600. Revise list of section as appropriate for specific project.)

1. Metal Framing: as specified in **[Section 05 40 00 - Cold-Formed Metal Framing]**
2. Sheathing: as specified in **[Section 06 16 00 - Sheathing]**

3.2 CEMENT BOARD INSTALLATION

(Specifier Note: PermaBASE Cement Board has been tested and/or approved for use in a variety of fire-rated wall assemblies - adjust the installation requirements when a rated wall is required for a specific project.)

- A. Fasten Cement Board horizontally or vertically through sheathing **[and weather barrier]** into framing.

1. Penetrate steel studs a minimum of 3/8 inch (9.53mm) with fastener.

(Specifier Note: Structural design may require fasteners be spaced closer)

2. Space fasteners 8 inches (20 cm) on center maximum along perimeter and in field of cement board unless noted otherwise.
3. Place fasteners a minimum of 3/8 inch (9.53 mm) and a maximum of 5/8 inch (16 mm) from the cement board edge.
4. Drive fastener heads flush with the face of the cement board.

- B. Stagger vertical joints of the cement board. Locate joints over framing members.

- C. Offset horizontal joints in cement board a minimum of 12 inches (30.48 cm) from horizontal joints in sheathing.

- D. Offset vertical joints in cement board a minimum of one stud space from vertical joints in sheathing.

- E. Offset joints in cement board a minimum of 8 inches from the corners of openings by "L" cutting cement board around openings.
- F. Treat cement board joints and corners with 4" wide alkali-resistant fiberglass mesh tape imbedded in LATICRETE® Polymer Fortified Veneer Mortar. Allow the taping treatment to cure for 12 to 24 hours at 70° F (21 °C).

3.3 SUBSTRATE TOLERANCES

(Specifier Note: Coordinate allowable tolerances with masonry manufacturer.)

- A. Maximum deviation in plane: Not to exceed 1/4 inch (6.35 mm) in 10 feet (3.05m), with not more than 1/16 inch (1.6 mm) variation in 1 foot (.305 m)

3.4 APPLICATION OF WEATHER BARRIER

- A. Comply with manufacturer's instructions and requirements of Division 7 Weather Barrier Section(s) for proper installation. Provide all required barrier materials, accessories, flashings, and other materials to seal all joints and penetrations and provide a complete weather barrier system.

3.5 INSTALLATION OF [THIN BRICK] [MANUFACTURED STONE] [NATURAL STONE VENEER]

(Specifier Note: Adhered masonry can be applied to the substrate in several ways.)

- A. Apply adhered masonry to substrate using polymer modified mortars as recommended by Masonry Veneer Mortar manufacturer.

OR

- B. Apply skim coat of modified dry-set mortar with a trowel to cover entire back of the veneer unit.
- C. Apply additional mortar to the back of the coated veneer unit sufficient to completely fill the space between the veneer unit and the substrate when compressed against the substrate.
- D. Press the mortar covered unit against the substrate at the desired final position. Slide the unit roughly 1 inch (25.4 mm) diagonally from the desired final position and back into place while maintaining even pressure to ensure space between veneer unit and substrate is filled.
- E. Clean excess extruded mortar with trowel and spread onto next veneer unit to be placed.

OR

- F. Key uniform layer of modified dry-set cement mortar to cement board substrate.
- G. Comb additional mortar onto substrate with mortar manufacturer recommended notched trowel.
- H. Back butter veneer units 8 inches by 8 inches and larger to provide full bedding of the veneer.
- I. Place veneer into the mortar and adjust to desired position.

- J. Clean excess extruded mortar

3.6 MASONRY POINTING

- A. Allow adhered masonry veneer to cure a minimum of 24 hours at 70 degrees F.
- B. Verify grout joints are free of dirt and debris, and remove any water standing in joints.
- C. Install pointing mortar to desired depth, ensuring mortar is forced into voids.
- D. Cure to "thumbprint" hardness and trowel, rake, or brush joint to **[V-groove]** **[insert desired]** finish.

3.7 FINISHING PENETRATIONS THROUGH ADHERED MASONRY

- A. Install closed cell backer rod in deep joints and bond breaker tape on shallow joints
- B. Protect veneer face by masking surface. Apply single component, neutral cure, 100% silicone sealant, as specified in Division 7 Joint Protection section(s), into joint or gap, filling completely.
- C. Finish joint for a smooth finish, ensuring sealant contact with sides of joint.
- D. Remove masking and clean veneer surface.

3.8 CLEANING

- A. Clean completed adhered masonry work after mortar is set in accordance with masonry and mortar manufacturers' recommended practices.

END OF SECTION

DISCLAIMER:

National Gypsum Company is the exclusive service provider of products manufactured by Gold Bond Building Products, LLC; PermaBASE Building Products, LLC and ProForm Finishing Products, LLC. Guide Specifications have been written as an aid to the professionally qualified specifier and design professional. The use of this information requires the professional judgment and expertise of the qualified specifier and design professional to adapt the information to the specific needs of the building Owner and the project; to coordinate with the design professional's construction document process, and to meet the applicable building codes, regulations and laws. National Gypsum Company on behalf of itself and the entities specified above, disclaims any warranty, express or implied, including the warranty of fitness for a particular purpose, of any product identified in the Guide Specifications.

© 2021 National Gypsum Services Company