Panel-Ty

The AR Panel-Ty is equipped with a head washer at each end and with a large loose-fitting washer at one end. Its function is to tie together the end-studs of adjacent panel forms. Available in a range of sizes based on stud requirements. Also available in water seal.

STANDARD 2.25M
APPROXIMATE SAFE
WORKING LOAD
10kN (2,250 LBS)
2:1 Safety Factor

