



BALLOONS

1.	OMG SpeedTite Roof Drain Mechanical Seal
2.	Drain Body
3.	Strainer Dome Retaining Clips
4.	Strainer Dome Nylon Push-in Fastener
5.	Aluminum Strainer Dome
6.	Sealant
7.	Thermoplastic Coated Aluminum Flange
8.	Welded Thermoplastic Flashing Target
9.	Existing Rain Water Leader
10.	Existing Cast Iron Drain Bowl
11.	Substrate
12.	Vapour Retarder (optional)
13.	Treated Wood Nailer (optional)
14.	Insulation (sloped to drain)
15.	Flange Fastener
16.	Wood Nailer Fastener
17.	25mm (1") Minimum Weld
18.	Thermoplastic Membrane
19.	OMG SpeedTite Roof Drain Vortex Breaker
20.	Hand-Turned Seal Activator

APPLICATIONS

THERMOPLASTIC ROOF MEMBRANES

SIZES:

3 INCH, 4 INCH, 5 INCH, 6 INCH

NOTES:

1-REFER TO ROOF MEMBRANE MANUFACTURER FOR THEIR APPROVED INSTALLATION DETAIL.

2-OMG SPEEDTITE ROOF DRAIN COMPLIES WITH ANSI/SPRI RD-1.



SpeedTite™

ROOF DRAINS

OMG Inc.
153 Bowles Road
Agawam, MA 01001
800-633-3800
info@olyfast.com
www.olyfast.com

NAME: TPO OMG SpeedTite Roof Drain/PVC OMG SpeedTite Roof Drain			
DRWN. BY: JLM	DATE:09/12/2015(R8)	SKU: AFRTP0_A (INSERT SIZE); AFRPVC_A (INSERT SIZE)	
APPD. BY: DG	DATE:09/15/2015	SCALE: NOT TO SCALE	SHEET: 1 OF 1